KOLAR DISTRICT.

NOTIFICATION.

The 16th February 1891.

It is hereby notified for public information that, under the provisions of Rule 13 of the Forest Rules of the 8th June 1878, the undermentioned State Forests and Plantations will be closed to the public for the hot season from this date up to 31st May 1891.

Shooting of any kind is entirely prohibited during the above period. All trespassers will be liable to prosecution :—

Number.	Name of State Forest or Plantation.	Taluk.
	Forests.	
1	Nundydroog Forest	Chikballapur.
2	Narasimhadevarabetta Forest	Do Goribidnur Taluks and Gudibanda Range.
3	Kamasandra jungles including plantations therein situated ..	Bowringpet and Malur.
4	Rayalpad, Nelavanki and Adagal Jungles do ..	Chintamani Taluk and Srinivaspur Range.
5	Srinivaspur and Yeldur Jungles do	Srinivaspur Sub-Taluk and Mulbagal Taluk.
6	Agara Jungles	Mulbagal.
7	Cheruvanahalli, Anajiganahalli and Hosur Pode	Srinivasapur Sub-Taluk.
	Plantations.	
8	Nundy	Chikballapur.
9	Sulalappanadinne	
10	Gajaldinne	Kolar.
11	Sangondahalli	
12	Malur	Malur.
13	Bichaganhalli	Gudibanda Sub-Taluk.
14	Patrenahalli	
15	Tirumalaiyanadinne	
16	Chaudasandra	Sidlaghatta.
17	Goramadagu	

C. MADIAH,
Dy. Commissioner.

KADUR DIVISION.

ADVERTISEMENT.

The 18th March 1891.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 5th April 1891, for Chikmagalur water-supply. A very rough estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of July 1892.

2. The plans, detailed estimate, and conditions may be seen at the Executive Engineer's Office at Chikmagalur between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Chikmagalur water-supply project;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Secretary to the Government of Mysore, Public Works Department, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items of Work.	Per.	Quantity.	Rate. Rs.	A.	P.
Constructing a new Impounding Reservoir.					
Grubbing out grass in reservoir site	Sq.				
Earthwork to bund including watering and consolidation ..	C. Yd.	55,453			
Puddling earthwork	Do	..			
Rough stone work new	Do	3,587			
Grade stones	No.	16			
Bench mark stones	Do	2			
Earthwork foundations	C. Yd.	200			
Burnt brick in surki mortar	C. Ft.	900			
Do ordinary mortar	Do	..			
Plastering in ordinary mortar	Sq.	10			
Plastering in surki mortar	Do	10			
Rough stone work new	C. Yd.	100			
Burnt stone slabs	S. Ft.	300			
Burnt stone in ordinary mortar	C. Ft.	*a*			
Concrete in ordinary mortar	Do	*a*			
Concrete in surki mortar	Do	*a*			
Drilling holes in slabs	Per hole.	*a*			
Plugs and rods	Each	*a*			
Excavating a new channel, constructing Filter beds, Service Reservoir, laying pipe, fixing Pillar fountains, &c.					
Earthwork to channel, all soils, except blasting ..	C. Yd.	33·450			
Blasting rock	Do	*a*			
Hard rocky soil requiring wedging out, &c.	Do	*a*			
Brick in surki mortar	C. Ft.	20·913			
Do ordinary mortar	Do	*a*			
Concrete ordinary	Do	*a*			
Do in surki	Do	*a*			
Burnt stone slabs	Do	1,218			
Plastering with surki mortar	Sq.	94·47			
Do ordinary mortar	Do	*a*			
Broken metal	C. Yd.	*a*			
Sand	Do	*a*			
Charcoal	Do	*a*			
Excavating trench for piping and refilling	Do	*a*			
Broken brick jelly	Do	*a*			
Laying pipes	R. Yd.	*a*			
Brick work without mortar	C. Ft.	*a*			
Mangalore piping perforated	R. Ft.	*a*			
Wooden shutters	C. Ft.	*a*			
Head joints	Each.	*a*			
Fixing street pillars	Do	*a*			
Do valves	Do	*a*			
Pointing in ordinary mortar	Sq.	*a*			
Pointing in surki mortar	Do	*a*			
Mile and furlong stones	No.	*a*			
Portland cement plastering	Sq.	*a*			
Wooden railing	P. R. Ft.	*a*			
Iron railing	R. Ft.	*a*			
Cornice work	Do	*a*			
Archwork small in ordinary mortar	C. Ft.	*a*			
Do in surki mortar	Do	*a*			
Rough stone dry new, apron or floor	C. Yd.	*a*			
Rough stone in ordinary mortar	Do	*a*			
Do in surki mortar	Do	*a*			

N. B.—(*a*) The quantities may be ascertained as soon as detailed estimates are ready. Rates may be quoted by tenderer for each class of work.

A. GOVINDACHARLU,
Executive Engineer.